

ARTICLE III. The statement of prevailing wages appearing in the General Prevailing Wage Rates is hereby specifically referred to and by this reference is made a part of this contract. It is further expressly agreed by and between the parties thereto that should there be any conflict between the terms of this instrument and the bid or proposal of said Contractor, then this instrument shall control and nothing herein shall be considered as an acceptance of the said terms of said proposal conflicting herewith.

ARTICLE IV. By my signature hereunder, as Contractor, I certify that I am aware of the provisions of Section 3700 of the Labor Code which require every employer to be insured against liability for workmen's compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with such provisions before commencing the performance of the work of this contract.

ARTICLE V. And the said Contractor agrees to receive and accept the following prices as full compensation for furnishing all materials and for doing all the work contemplated and embraced in this agreement; also for all loss or damage, arising out of the nature of the work aforesaid, or from the action of the elements, or from any unforeseen difficulties or obstructions which may arise or to be encountered in the prosecution of the work until its acceptance by the Department of Transportation and Public Works, and for all risks of every description connected with the work; also for all expenses incurred by or in consequence of the suspension or discontinuance of work and for well and faith-fully completing the work, and the whole thereof, in the manner and according to the plans and specifications and the requirements of the Engineer under them, to wit:

ENGINEER'S ESTIMATE

RIVER ROAD CHANNELIZATION AND
RIVER ACCESS PROJECT AT SUNSET BEACH

C03410

ITEM NO.	S/ F	ITEM CODE	ITEM DESCRIPTION	UNIT	QTY.	UNIT PRICE	ITEM TOTAL
1		071325	TEMPORARY FENCE (ESA)	LF	1,327.00		
2		074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	1.00		
3		074020	WATER POLLUTION CONTROL	LS	1.00		
4		074021A	WATER POLLUTION CONTROL MAINTENANCE	LS	1.00		
5		120090	CONSTRUCTION AREA SIGNS	EA	4.00		
6		120100	TRAFFIC CONTROL SYSTEM	LS	1.00		
7		120101	FLAGGING	FA	38,000.00	\$1.00	\$38,000.00
8		128650	PORTABLE CHANGEABLE MESSAGE SIGN	DY	75.00		
9		150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	300.00		
10		153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SY	670.00		
11		160101	CLEARING AND GRUBBING	LS	1.00		
12		170101	DEVELOP WATER SUPPLY	LS	1.00		
13		190101	ROADWAY EXCAVATION	CY	1,617.00		
14		190110	LEAD COMPLIANCE PLAN	LS	1.00		
15		190122	ROADWAY EXCAVATION (HAZARDOUS MATERIAL) CLASS I	CY	75.00		
16		190123	ROADWAY EXCAVATION (HAZARDOUS MATERIAL) CLASS II	CY	75.00		
17		190124	ROADWAY EXCAVATION (HAZARDOUS MATERIAL) CLASS III	CY	200.00		

18	190166	UNSUITABLE MATERIAL EXCAVATION	CY	50.00		
19	194001	DITCH EXCAVATION	CY	130.00		
20	198001	IMPORTED BORROW	CY	1,896.00		
21	198022	LOCAL BORROW	CY	5,872.00		
22	203011	EROSION CONTROL (TYPE C)	SY	4,253.00		
23	203016	EROSION CONTROL (TYPE D)	SY	9,148.00		
24	260201	CLASS 2 AGGREGATE BASE	CY	2,154.00		
25	390205	AGGREGATE (TYPE A, ASPHALT CONCRETE, 3/4" MAXIMUM GRADING)	TN	2,690.00		
26	391001	PAVING ASPHALT (ASPHALT CONCRETE)	TN	145.00		
27	394001	PLACE ASPHALT CONCRETE DIKE (TYPE A)	LF	937.00		
28	394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	SY	3,508.00		
29	510048	CONCRETE BOX EXTENSION WITH WING WALLS	LS	1.00		
30	510049	CONCRETE RETAINING WALL	LS	1.00		
31	562000	ROADSIDE SIGNS	EA	6.00		
32	620101	18" ALTERNATE PIPE CULVERT (TYPE A)	LF	527.00		
33	707050	DRAINAGE INLET (TYPE GO)	EA	2.00		
34	707083	PRECAST CONCRETE INLET (24" X 24") W/ OPENING	EA	1.00		
35	721008	ROCK SLOPE PROTECTION (LIGHT, METHOD B)	CY	16.00		
36	721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	CY	5.00		
37	721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	CY	10.00		
38	729011	JUTE MESH (DITCH LINING)	SY	175.00		
39	729003	EROSION CONTROL BLANKET (DITCH LINING)	SY	175.00		
40	750012	STEEL COVER (24"X24")	EA	1.00		
41	750034	INLET GRATE (TYPE 24-12X)	EA	2.00		
42	800028	FENCE (TYPE 1)	LF	667.00		
43	800029	FENCE (TYPE 2)	LF	1,123.00		
44	800030	FENCE (TYPE 3)	LF	400.00		
45	800031	FENCE (TYPE 4)	LF	396.00		
46	800032	FENCE (TYPE 5)	LF	78.00		
47	801338	12" PIPE GATE	EA	2.00		
48	801339	40" PIPE GATE	EA	1.00		
49	810110	SURVEY MONUMENT	EA	2.00		
50	832002	METAL BEAM GUARD RAILING (STEEL POST)	LF	1,346.00		
51	839541	TRANSITION RAILING (TYPE WB)	EA	4.00		
52	839552	TERMINAL SECTION (TYPE C)	EA	2.00		
53	839559	TERMINAL SYSTEM (TYPE ET)	EA	2.00		

54	839565	TERMINAL SYSTEM (TYPE SRT)	EA	1.00		
55	840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	8,322.00		
56	840506	8" THERMOPLASTIC TRAFFIC STRIPE	LF	284.00		
57	840509	12" THERMOPLASTIC TRAFFIC STRIPE	LF	60.00		
58	840515	THERMOPLASTIC PAVEMENT MARKING	SF	86.00		
59	840653	PAINT TRAFFIC STRIPE	LF	872.00		
60	840660	PAINT PAVEMENT MARKING	SF	46.00		
61	842000	PARKING BUMPER (PRECAST CONCRETE)	EA	33.00		
62	850102	PAVEMENT MARKER, REFLECTIVE	EA	175.00		
63	860799	RELOCATE AND INSTALL ELECTRIC SERVICE	LS	1.00		
64	998109	RELOCATE AND INSTALL WATER LINE	LS	1.00		
65	999997	TRENCH SHORING AND BRACING	LS	1.00		
66	999998	GUARANTY	LS	1.00		
TOTAL						

ARTICLE VI. The County's Board of Supervisors has awarded this contract to the Contractor on the basis of the Contractor's base bid (Items _____ through _____), in accordance with the contract documents as modified by Addenda(um) No(s). _____.

ARTICLE VII. For the work covered by this contract, the County agrees to pay and the Contractor agrees to accept the sum of _____, subject to adjustment on the basis of the unit prices set forth in the Contractor's bid.

Attention is directed to paragraph three of Section 9-1.06, "Partial Payments," of the Standard Specifications regarding "retention of funds":

"The Department shall retain 10% of the estimated value of the work done and 10% of the value of materials so estimated to have been furnished and delivered and unused or furnished and stored as aforesaid as part security for the fulfillment of the contract by the Contractor, except that at any time after 20 percent of the work has been completed, if the Engineer finds that satisfactory progress is being made, the Department may reduce the total amount being retained from payment pursuant to the above requirements to 5 percent of the total estimated value of the work and materials and may also reduce the amount retained from any of the remaining partial payments to 5 percent of the estimated value of the work and materials. In addition..."