

**COUNTY OF SONOMA
DEPARTMENT OF TRANSPORTATION
AND PUBLIC WORKS**

2300 COUNTY CENTER DRIVE, SUITE B 100
SANTA ROSA, CALIFORNIA 95403

Phillip M. Demery, Director



AREA CODE (707)
ROADS565-2231
TRANSIT.....585-7516
REFUSE565-7940
AIRPORT.....565-7243
AIR POLLUTION433-5911
FAX565-2620
www.sonomcountypublicworks.com

November 18, 2009

**NOTICE TO PLANHOLDERS
FOR CONSTRUCTION OF**

FEDERAL AID PROJECT NO. CML-5920 (112)

**WESTERN AVENUE
BIKE SHOULDER WIDENING**

COUNTY PROJECT NO. C03020

ADDENDUM NO. 1

I. Changes to the Contract Plans:

On Plan Sheet 8, the Structure Summary has been changed to include new Item No. 40 and to correct the quantity for "Inlet Frame and Grate (24"x24")."

On Plan Sheet 9, the Water Facilities Summary has been changed to eliminate the "Lower Water Main," "Relocate Water Service" and "Extend/Replace Water Service Pipe" items of work. The quantity for "Relocate Water Service (Complete)" has been changed. The item "Relocate Private Water Service Lines" has been added.

On Plan Sheet 9, the Guard Rail Summary has been changed and a "Guard Rail Driveway Radius Detail" has been referenced (Attachment C).

II. Changes and Additions to the Contract Special Provisions:

On Page SP-57, the second paragraph of Section 10-1.23, A. Relocate Water Service (Complete), is revised to read: "The contract price paid for relocate water service (complete) shall include full compensation for furnishing all labor, materials including water pipe, tools, equipment, and incidentals and for doing all of the work involved in relocate water service (complete) in place, including reconnecting meters to the private service lines, replacing service saddles and corporation stops. Meters, if required, will be supplied by the City of Petaluma.

On Page SP-57, Section 10-1.23, B. Relocate Water Service, is deleted.

On Pages SP-57 and SP-58, Section 10-1.23, C. Extend/Replace Water Service Pipe, is deleted.

On Page SP-58, Section 10-1.23, D., Lower Water Main, is deleted.

Add Section 10-1.23, B., Relocate Private Water Service Lines as follows:

B. RELOCATE PRIVATE WATER SERVICE LINES: This work shall consist of replacing and relocating existing private water service lines beginning at existing meters at the most westerly end of the City of Petaluma water main and continuing in a westerly direction to a point within the project limits.

The contract price paid for relocate private water service lines shall include full compensation for furnishing all labor, materials including water pipe, tools, equipment, and incidentals, and for doing all of the work involved in relocate private water service lines including reconnecting meters to the new service lines.

III. Changes, Deletions and Additions to the Engineer's Estimate in the Special Provisions and Bidder's Book:

Original Item No. 14, "Relocate Water Service" is deleted.

Original Item No. 15, "Extend/Replace Water Service Pipe" is deleted.

Original Item No. 16, "Lower Water Main" is deleted.

New Item No. 14, "Relocate Private Water Service Lines" is added.

New Item No. 55, "Terminal Section (Type C)" is added.

The quantity for Original Item No. 45, "24"x24" Precast Concrete Inlet, is changed to 4 each.

The quantity for Original Item No. 46, "24"x36" Precast Concrete Inlet, is changed to 5 each.

The quantity for Original Item No. 47, "36"x36" Precast Concrete Inlet, is changed to 10 Each.

The quantity for Original Item No. 49, "Inlet Frame and Grate (24"x24") is changed to 4 each.

The quantity for Original Item No. 50, "Inlet Frame and Grate (24"x36") is changed to 5 each.

The quantity for Original Item No. 51, "Inlet Frame and Grate (36"x36") is changed to 9 each.

The quantity for Original Item No. 54, "Metal Beam Guard Railing (Steel Post)" is changed to 464.50 lf.

The quantity for Original Item No. 56, “Terminal System (Type SRT)” is changed to 9 each.

The quantity for Original Item No. 57, “” is changed to 9 each.

The addition and deletion of new items in the Engineer’s Estimate has caused some of the items to renumber. Please refer to the revised estimates.

Please replace the following “Copy of Bid Item List”, in the Special Provisions and the two “Engineer’s Estimate” in the Bidder’s Book, per the attached revised pages (Attachment B)

Pages B-1 and B-2 of the Special Provisions is replaced with the “Copy of Bid Item List” B-1(Add 1) and B-2(Add 2).

Pages BB-4, BB-5, and BB-6 are replaced with the “Engineer’s Estimate” BB-4(Add 1), BB-5(Add 1) and BB-6 (Add 1).

Pages BB-31, BB-32, and BB-33 are replaced with the “Engineer’s Estimate” BB-31(Add 1), BB-32(Add 1) and BB-33(Add 1).

Please fill out the Addendum Acknowledgement sheet on Page BB-7 of the Bidder’s Book verifying your receipt of this Addendum and submit with your bid.

Original Signed

Levi Gurule, P.E.

Attachment A - Contract Plan Sheets 8 and 9

Attachment B - Copy of Bid Item List and Engineer’s Estimate

Attachment C - Guard Rail Driveway Radius Detail