

COUNTY OF SONOMA
DEPARTMENT OF TRANSPORTATION
AND PUBLIC WORKS
2300 COUNTY CENTER DRIVE, SUITE B 100
SANTA ROSA, CALIFORNIA 95403

Phillip M. Demery, Director



AREA CODE (707)
ROADS..... 565-2231
TRANSIT 585-7516
REFUSE 565-7940
AIRPORT..... 565-7243
AIR POLLUTION..... 433-5911
FAX..... 565-2620
www.sonoma-county.org/tpw

October 7, 2010

NOTICE TO PLANHOLDERS
FOR CONSTRUCTION OF

**HIGHWAY 12 EARTH SHOULDER WIDENING
AT LAS PALMAS SUBDIVISION
COUNTY PROJECT NO. C10003**

ADDENDUM NO. 1

I. Changes to the Special Provisions:

- A. Insert the attached Standard Plans List after the Typical Section.
- B. Page SP-12, Section 5-1.27, PROJECT INFORMATION, delete the sentence "Cross sections are available for this project in paper copy."
- C. Section 10-1.21D, IMPORTED BORROW, is amended with the following paragraph:
Imported Borrow used shall be of low to non-expansive nature and should meet the following criteria:

Plastic Limit	less than 12
Liquid Limit	less than 35
Percent Soil Passing #200 Sieve	between 15% and 35%
Maximum Aggregate Size	4 inches

Please fill out the Addendum Acknowledgement sheet on page BB-5 of the Bidder's Book verifying your receipt of this Addendum and submit with your bid.

_____ original signed _____
Rex Cummins, P.E.

Attachment A - Standard Plans List

Standard Plans List

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. Applicable Revised Standard Plans (RSP) and New Standard Plans (NSP) indicated below are included in the project special provisions.

PAVEMENT MARKERS, TRAFFIC LINES, AND PAVEMENT MARKINGS

A10C	Symbols
A10D	Symbols
A20D	Pavement Markers and Traffic Lines, Typical Details
EXCAVATION AND BACKFILL	
A62A	Excavation and Backfill – Miscellaneous Details
A62B	Limits of Payment for Excavation and Backfill – Bridge Surcharge and Wall
A62D	Excavation and Backfill – Concrete Pipe Culverts
RSP A62DA	Excavation and Backfill – Concrete Pipe Culverts
OBJECT MARKERS, DELINEATORS, CHANNELIZERS AND BARRICADES	
A73A	Object Markers
A73B	Markers
A73C	Delineators, Channelizers and Barricades
DRAINAGE INLETS, PIPE INLETS AND GRATES	
D73	Drainage Inlets
NSP D73A	Drainage Inlets (Precast)
D74C	Drainage Inlets Details
RSP D77A	Grate Details
D77B	Bicycle Proof Grate Details
GUTTER AND INLET DEPRESSIONS	
D78A	Gutter Depressions
CONSTRUCTION LOADS ON CULVERTS AND STRUT DETAILS	
D88	Construction Loads on Culverts
D94B	Concrete Flared End Sections
PIPE COUPLING AND JOINT DETAILS	
D97H	Reinforced Concrete Pipe or Non-Reinforced Concrete Pipe – Standard and Positive Joints
TEMPORARY CRASH CUSHIONS, RAILING AND TRAFFIC SCREEN	
T3	Temporary Railing (Type K)
TEMPORARY TRAFFIC CONTROL SYSTEMS	
T13	Traffic Control System for Lane Closure on Two Lane Conventional Highways
T17	Traffic Control System for Moving Lane Closure on Two Lane Conventional Highways
TEMPORARY WATER POLLUTION CONTROL	
T59	Temporary Water Pollution Control Details (Temporary Concrete Washout Facility)
NSP T61	Temporary Water Pollution Control Details (Temporary Drainage Inlet Protection)
NSP T62	Temporary Water Pollution Control Details (Temporary Drainage Inlet Protection)