

**COPY OF BID ITEM LIST**  
(Not to be used for bidding purpose)

<b>Healdsburg Transfer Station Scalehouse and Scale Improvements – WO6957</b>				
<b>Item</b>	<b>Description</b>	<b>Applicable Specification Section</b>	<b>Quantity</b>	<b>Units</b>
1	Mobilization / Demobilization	Div. IV Section 01270	1	LS
2	Traffic Control	Div. IV Section 01570	1	LS
3	Flagging	Div. IV Section 01570	2,000	FA
4	Demolition and Disposal of Existing AC Pavement	Div. IV Section 02221	20,250	SF
5	Removal of Existing Propane Tank Enclosure	Div. IV Section 02221 and Sheet 4	1	LS
6	Bulk Excavation	Sheets 2, 5, 7, 12, 13	6,450	CY
7	Install Temporary Roads	Sheet 4	200	CY
8	Removal of Existing Scale and Foundation	Div. IV Section 02221	1	LS
9	Demolition and Disposal of Existing Scalehouse and Foundation	Div. IV Section 02221	1	LS
10	Relocate Affected Existing Utilities (waterline, phone line, electrical line)	Div. IV Section 16050, 16123 and Sheet 14	400	LF
11	Install Traffic-Rated Cover and Protect Existing Septic Tank	Sheet 4	1	EA
12	Protect, Lower, and Replace Existing Sewer Clean Out	Sheet 4	1	EA
13	Replace Existing Electric and Phone Vaults with Traffic-Rated Vaults	Sheet 4	2	EA
14	Install 4-inch PVC Sch 40 Scalehouse Drain	Sheets 6, 10, 11, A3.0	65	LF
15	Install 4-inch PVC Sch 40 Truck Scale Drains	Sheets 6, 10, 0015-1B	120	LF
16	Install 1-inch and 2-inch PVC Sch 80 Future Irrigation Supply	Sheets 6 & 10	80	LF
17	Install 2-inch PVC Sch 80 Water and 1.5-inch PVC Sch 80 Sewer to Scalehouse from Existing Services	Sheets 6 & 10	280	LF
18	Install 4 (four) 2-inch PVC Sch 80 Conduits for Telephone and Alarm to Scalehouse from Existing Services	Div. IV Sections 16050, 16123 and Sheets 6, 10, 14	210	LF

<b>Healdsburg Transfer Station Scalehouse and Scale Improvements – WO6957</b>				
<b>Item</b>	<b>Description</b>	<b>Applicable Specification Section</b>	<b>Quantity</b>	<b>Units</b>
19	Install 2 (two) 2-inch and 1 (one) 3-inch PVC Sch 80 Electrical Conduits from Power Pole to Scalehouse	Div. IV Sections 16050, 16123 and Sheets 6, 10, 14	240	LF
20	Place 12-inch Aggregate Base	Div. IV Section 02315 and Sheet 8	31,500	SF
21	Place 3-inch Asphalt Concrete	Div. IV Section 02740 Sheet 8	400	TN
22	Erosion Control	Div. IV Section 02250	31,500	SF
23	Apply Traffic Striping	Div. IV Section 02760 and Sheet 9	1	LS
24	Install Signs	Sheet 9	1	LS
25	Building Foundation	Div. IV Section 03300 and Sheets 11, A3.0, S1.0	1	EA
26	Prefabricated Building	Div. IV Section 13128 and Sheets A-2, A-3, S1.0	1	EA
27	Hookup Utilities at Prefabricated Building	Div. IV Section 15400 and 16050	1	EA
28	Sewage Tank/Effluent Pumping Package	Div. IV Section 02532 and Sheets 6 & 11	1	EA
29	Power Pole and Meter Main with Transfer Switch	Sheet 14	1	EA
30	Install New Scale Foundations and Aprons	Div. IV Section 11715 and Sheets 5, 0015-1B & 2B	2	EA
31	Install New Scales	Div. IV Section 11715	2	EA
32	Electrical Wire and Cable	Div. IV Section 16123, 16130 and Sheet 14	275	LF
33	Install New Concrete Curb	Div. IV Section 03300 and Sheet 9	80	LF