

ATTACHMENT 1

**BID SCHEDULE
AIP PROJECT NO. 3-06-0241**

BID SCHEDULE A

Item No.	Description	Unit	Total Quantity	Unit Cost	Extension
1	Mobilization	LS	1	\$	\$
2	SWPPP	T&M	1	\$ 5,000.	\$ 5,000.
3	Contaminated Soils Removal Allowance	T&M	1	\$100,000.	\$100,000.
4	Airfield Traffic and Safety Control	LS	1	\$	\$
5	Taxiway Z Earthwork and Site Preparation	LS	1	\$	\$
6	East Taxilane Earthwork and Site Preparation	LS	1	\$	\$
7	Electrical Demolition	LS	1	\$	\$
8	Pavement Pulverization and Blend	SY	8,875	\$	\$
9	Geogrid Fabric	SY	1,200	\$	\$
10	Recycled Subbase	CY	800	\$	\$
11	Recycled Shoulder Base	SY	2,110	\$	\$
12	AC Pavement Join/Transition Grind	SY	3,100	\$	\$
13	Lime Treated Subgrade (P-155)	SY	8,300	\$	\$
14	Aggregate Base (P-209)	CY	3,000	\$	\$
15	Asphalt Concrete (P-401)	TON	2,800	\$	\$
16	Asphalt Concrete Leveling Course (P-401)	TON	135	\$	\$
17	Bituminous Prime Coat (P-602)	TON	8	\$	\$
18	No. 8 5,000 Volt Cable	LF	2,950	\$	\$
19	Trench and Backfill – Native	LF	2,240	\$	\$
20	2-Inch PVC Conduit	LF	2,010	\$	\$
21	Two 2-Inch PVC Duct Banks, Concrete Encased	LF	235	\$	\$
22	Electrical Pullbox	EA	4	\$	\$
23	L-861 MITL LED, Elevated	EA	30	\$	\$
24	Adjust MITL	EA	7	\$	\$
25	Relocated Lighted Guidance Sign	EA	1	\$	\$
26	Pavement Marking Yellow with Reflective Media	SF	4,100	\$	\$
27	Erosion Control	T&M	1	\$ 25,000.	\$
TOTAL					\$

Total Bid Schedule A (Items 1 through 27). Please indicate in writing:

BID ALTERNATE A

Item No.	Description	Unit	Total Quantity	Unit Cost	Extension
BA-1A	Caltrans Asphalt	TON	2,935	\$	\$
BA-2A	Delete Item 15 Asphalt Concrete (P-401)	TON	-2,800	\$	(\$)
BA-3A	Delete Item 16 Asphalt Lev. Course (P-401)	TON	-135	\$	(\$)
TOTAL					\$

Total Bid Alternate A (Item BA-1A through BA-3A). Please indicate in writing:

BID SCHEDULE B

Item No.	Description	Unit	Total Quantity	Unit Cost	Extension
1	Mobilization	LS	1	\$	\$
2	SWPPP	T&M	1	\$ 5,000.	\$ 5,000.
3	Contaminated Soils Removal Allowance	T&M	1	\$100,000.	\$100,000.
4	Airfield Traffic and Safety Control	LS	1	\$	\$
5	Taxiway Z Earthwork and Site Preparation	LS	1	\$	\$
6	East Taxilane Earthwork and Site Preparation	LS	1	\$	\$
7	Apron A Site Preparation	LS	1	\$	\$
8	Electrical Demolition	LS	1	\$	\$
9	Pavement Pulverization and Blend	SY	8,875	\$	\$
10	5-Foot Wide PCC Valley Gutter	SY	225	\$	\$
11	Geogrid Fabric	SY	1,200	\$	\$
12	Recycled Subbase	CY	800	\$	\$
13	Recycled Shoulder Base	SY	2,110	\$	\$
14	AC Pavement Join/Transition Grind	SY	3,800	\$	\$
15	Lime Treated Subgrade (P-155)	SY	8,300	\$	\$
16	Aggregate Base (P-209)	CY	3,000	\$	\$
17	Asphalt Concrete (P-401)	TON	11,500	\$	\$
18	Asphalt Concrete Leveling Course (P-401)	TON	61	\$	\$
19	Bituminous Prime Coat (P-602)	TON	8	\$	\$
20	Paving Fabric	SY	39,950	\$	\$
21	Drainage Structure Adjustments	LS	1	\$	\$
22	No. 8 5,000 Volt Cable	LF	2,950	\$	\$
23	Trench and Backfill – Native	LF	2,240	\$	\$
24	2-Inch PVC Conduit	LF	2,010	\$	\$
25	Two 2-Inch PVC Duct Banks, Concrete Encased	LF	235	\$	\$
26	Electrical Pullbox	EA	4	\$	\$
27	L-861 MITL LED, Elevated	EA	30	\$	\$
28	Adjust MITL	EA	7	\$	\$
29	Relocated Lighted Guidance Sign	EA	1	\$	\$
30	Relocated Apron Area Light	EA	2	\$	\$
31	Aircraft Tiedown Anchor	EA	30	\$	\$
32	Pavement Marking Yellow with Reflective Media	SF	7,900	\$	\$
33	Erosion Control	T&M	1	\$ 25,000.	\$
TOTAL					\$

Total Bid Schedule B (Items 1 through 33). Please indicate in writing:

BID ALTERNATE B

Item No.	Description	Unit	Total Quantity	Unit Cost	Extension
BA-1B	Caltrans Asphalt	TON	11,561	\$	\$
BA-2B	Delete Item 17 Asphalt Concrete (P-401)	TON	-11,500	\$	(\$)
BA-3B	Delete Item 18 Asphalt Lev. Course (P-401)	TON	-61	\$	(\$)
TOTAL					\$
Total Bid Alternate B (Item BA-1B through BA-3B). Please indicate in writing:					

Acknowledgement of Addenda

Acknowledgment of Addenda

Addendum No. Initial

Signature/Title

Company

Contractor's License Number/Expiration Date

NOTE: Contractor License Number and Expiration Date stated herein are made under penalty of perjury.